



SOURCE FOR STREAM

2023 Conference

Canada's Premier
Stormwater and Erosion
and Sediment Control
Conference

Thank you to our sponsors!

EXECUTIVE SPONSORS



Canadian Society for
Civil Engineering



Société canadienne
de génie civil



OPPORTUNITIES SPONSOR



MEDIA SPONSORS



HOSTS

Presented by:



In association with:





Unique Implementation Challenges of Installing Large Corridor Channel Realignment: Too Much Dirt, Too Much Water, and Not Enough Time

Source to Stream Conference • March 23, 2023

Lindsay Davis, P. Geo, M.Sc., CAN-CISEC
Michael Lawson, B.Sc., C.E.T., CAN-CISEC, EP

Overview



- Discuss balancing environmental timing windows and site constraints during construction in large-scale corridor construction
- Phasing construction to keep project moving forward towards completion
- Implementing a design through staged channel and corridor activation

Natural Channel Construction Considerations



Construction Initiation

- Involvement of larger project team for site-wide activities to determine the most appropriate phasing approaches
- Construct water diversion facilities (i.e., temporary diversion channel) and install ESC measures
- Commence construction and ensure conformance to the drawings as work progresses to limit any timely or costly setbacks



Natural Channel Construction Considerations



Active Construction Period

- Working within the floodplain requires careful consideration of construction timing and water management
- Communicating with stakeholders to ensure that timelines and environmental constraints are adhered to
- Phasing works across multiple fisheries windows requires detailed planning



Natural Channel Construction Considerations



Phasing Work to Facilitate Future Phases

- Planning and communicating a phased approach to satisfy the client's needs and the regulatory agencies interests
- Ensuring the integrity of the channel is maintained and stable
- Preparing the site for a shutdown period and commencement of floodplain works



Natural Channel Construction Considerations



Completion of Natural Channel Corridor

- Successfully completing the final stage of works while limiting environmental impacts
- Managing the final stages to ensure that conformance of the design is met to the satisfaction of all project disciplines
- Creating a natural channel corridor design that will provide improved habitat for aquatic and terrestrial species

Natural Channel Design



Design practice that mimics geomorphic and ecological functions

- Replace degraded channels with naturalized watercourses
- Offers significant improvements to channel form and function
- Wetland habitat creation

Channel Diversion and ESC Measures



Temporary Diversion Channel

- Maintains flows downstream of the site allowing work to be completed in dry conditions and without interference to the existing watercourse



Channel Diversion and ESC Measures



Sediment control around perimeter of the work area

- Protects natural areas and reduces sediment inputs to the floodplain from site earthworks
- Needs to be installed correctly and function as anticipated
- Requires monitoring, maintenance and modification



Channel Corridor Construction



Initial Construction Activities

- Mass excavation of the corridor creates excess cut material for the site
- Typically completed by an earthworks contractor
- Consideration of water management as the excavation impounds water from precipitation events
- Coordination with landscape contractor to minimize extent of exposed soils

Channel Corridor Construction



Low flow Channel Works

- Completed offline with a temporary diversion channel
- Further excess soil is created necessitating additional stockpiling needs
- Maintaining a dry work area requires water management techniques (i.e., cut-off swales, sediment basins, Hickenbottom® outlets, etc.)



Environmental Constraints and Site Works



Various windows create critical scheduling and coordination

- Environmental windows are the primary driver for the schedule of channel works
- Other site works can impact the timing required for environmental windows and delay progress
- Consideration of a phased activation approach for large scale corridors that cannot be completed in one construction season

Environmental Constraints and Site Works	January	February	March	April	May	June	July	August	September	October	November	December
Warmwater Fishery Window	Blue	Blue	Blue				Blue	Blue	Blue	Blue	Blue	Blue
Breeding Bird Window	Green	Green	Green						Green	Green	Green	Green
Landscape Works			Yellow	Yellow	Yellow	Yellow	Yellow	Yellow	Yellow	Yellow	Yellow	Yellow
Earthworks and Servicing *Weather dependent			Orange	Orange	Orange	Orange	Orange	Orange	Orange	Orange	Orange	Orange

Initial Phase of Channel Construction



- Best Management Practices used in all phases of construction



Initial Phase of Channel Construction



- Ensuring all specified materials are inspected and confirmed prior to installation



Initial Phase of Channel Construction



- Low flow channel and corridor designed to provide capacity for flooding during storm events



Initial Phase of Channel Construction



- Coordination with other development site works was required



Initial Phase of Channel Construction



November 2021

Interim Phase of Channel Construction



- Proper installation of erosion control measures prevents loss of topsoil and seed, and provides stability to channel banks



Interim Phase of Channel Construction



- Using 100% biodegradable materials
- Specifications differ between products so it is important to review products prior to installation
- Proper installation with continuous soil contact and secured with an adequate number of biodegradable stakes



Interim Phase of Channel Construction



Bypass pumping during flow activation stages

- Channel and floodplain stabilization completed prior to flow activation
- Contractor to complete this phase as efficiently as possible
- Intake and discharge areas setup to prevent impacts to water quality and fish

Interim Phase of Channel Construction



March 2022

Final Phase of Channel Construction



- Vegetation can establish within limits of low flow channel prior to and during habitat feature installation and landscaping



Final Phase of Channel Construction



- Complete the final works in sections to limit negative impacts to the receiving watercourse



Final Phase of Channel Construction



- Supplemental watering to promote vegetation establishment and prevent die-off



Final Phase of Channel Construction



June 2022

Post-Construction Results



- Channel design is completed with a fully stabilized corridor before the end of the growing season



Post-Construction Results



- Habitat features are established within the corridor complete with a fully functional low flow channel



Post-Construction Results



October 2022

Conclusion



- Progression of the development site works and environmental requirements in large-scale corridor channel construction can be achieved simultaneously
- Phasing construction to keep project moving forward and towards completion requires effective communication with regulatory agencies
- Successful implementation of a design through phased channel and corridor activation

Thanks to the entire team that helped make this project a success



Questions?



SOURCE FOR STREAM

2023 Conference

Canada's Premier
Stormwater and Erosion
and Sediment Control
Conference

Thank you to our sponsors!

EXECUTIVE SPONSORS



Canadian Society for
Civil Engineering



Société canadienne
de génie civil



OPPORTUNITIES SPONSOR



MEDIA SPONSORS



HOSTS

Presented by:



In association with:

