


## **Gambling on Site Conditions- Risks in Stream Restoration**





SOURCE TO STREAM CONFERENCE, BRAMPTON, ON HEATHER AMIRAULT, P.ENG., MICHAEL DHANRAJ, C.TECH. MARCH 27, 2025



Gambling on Site Conditions- Risks in Stream Restoration

## Agenda

- 1. Uncertainty vs Risk
- 2. Taking Risks
- 3. Managing Risks
- 4. Project Examples and Outcomes
- 5. Takeaways

2025

 $\vdash$ 

S 0  $\vdash$ 

SOURCE

ŝ

0 2

Ľ

URC

0


## **Uncertainty vs Risk**

#### **Uncertainty**

Probabilities and outcomes are unknown and unpredictable.

#### <u>Risk</u>

Probabilities of the possible outcomes are known.



2025

ΕAΜ

STR

10

SOURCE

## **Taking Risks**

- Budget
- Schedule
- Resources
- Site Conditions



## **Managing Risks**

 $\rightarrow$  Pushes the risk into the construction phase

Management techniques:


- Include provisional items in tender packages
- Have a contingency budget
- Have a flexible schedule



## **Managing Risks**

It's ok to take risks, as long as you know you're taking them.

- Understand the risk involved.
- Weigh the options & consider potential outcomes
- Only take "calculated risks"
- Inform client of relevant risks



## **Excess Soil Management**

#### Scenario:

• Soils testing during design vs. soils testing during construction

### Mitigation:

Determine acceptable risks based on:

- Quantity of soil and receiver(s)
- # of tests during design vs during construction
- Inclusion of contingency / provisional items



## **Excess Soil Management**

#### **Risk:**

- Testing during design adds clarity, allows for more accurate cost estimate
  - May still encounter unexpected soil conditions
- Postpone testing to construction phase
  - May encounter unexpected soil conditions
  - Not having right receivers lined up
  - Costs increasing from bid



## **Excess Soil Management**

#### **Remaining Risks:**

- Receiver may require additional testing
- Unexpected encounters are always
  possible
- Receivers can have tight windows for receiving soils





## Brierwood Creek (Weather/Construction Timing)

#### **Background:**

- Erosion on outer meander bend threatening rural road
- Proposed channel realignment
- Proponent plans construction for late fall, into winter

### **Risks**:

- Late fall winter construction
- Inexperienced contractor



## Brierwood Creek (Weather/Construction Timing)

#### **Mitigation:**

- Water management system + back up system
- Experienced construction inspector on site full time

#### Outcome:

- Slow construction, impeded by weather and undersized construction equipment
- Weather impacts during construction required repairs in spring

## Rock Lake (Material Sourcing)

### Background:

- Shoreline erosion
- Design stone armoring to mitigate erosion

### **Risks**:

- Estimating costs without complete understanding of local market
- Local sources may not be available, increasing bid costs
- Contractor may assume an "equivalent" material in bid



# **Rock Lake (Material Sourcing)**

#### Outcome:

- Source for specified material was not close to project site
- Material transportation to project site cost more than estimated,
- Client had to apply for further grant funding, delaying project start



C

0

# Long Lake (Site Conditions)

#### **Background:**

- Removal of the Water Control Structure (WCS)
- Restore the river channel to its natural state and improve fish passage
- Remote site, difficult access
- Design needed for permitting

## **Risk:**

- Design based on limited site information
- Managing client expectations of design and construction



# Long Lake (Site Conditions)

### Mitigation:

- Experienced construction inspector on site full time
- Inclusion of 'field fit' language on drawings and permit applications
- Some materials available outside of immediate project footprint
- Recommendation of contingency
  budget






## Long Lake (Site Conditions)

#### Outcome:

- Encountered unexpected field conditions: Insufficient material to complete riffle
- Required material imports & access route improvements
- Significant impact to project budget and schedule – time pressure to do 'something'
- Field fit solution may not result in required fish passage



## **Risks (Other)**

#### Utilities




#### LIDAR / Surface Data



Communication

Geotechnical



## Takeaway

It's ok to take risks, as long as you know you're taking them.

#### **Risk Management:**

- Weigh the options- consider potential outcomes
- Only take "calculated risks"
- Include contingency in tenders
- Inform clients of relevant risks early in design
- Include experienced personnel in construction phase





## **Questions?**

heather.amirault@stantec.com

michael.dhanraj@stantec.com





